

TREATMENT PLANT APPROVAL 13/2020

Plumbing and Drainage Act 2018

Approval

- The Aqua-Nova model 10114Z ("the system") described in the Specifications and Drawings in the attached Schedule and manufactured by Everhard Industries Pty Ltd (ABN 41 009 690 859) ("the manufacturer") has been assessed in accordance with the Queensland Plumbing and Wastewater Code (QPW Code) dated 26 October 2017.
- 2. Approval is granted for the advanced secondary quality wastewater treatment system, subject to compliance by the manufacturer with the requirements of the *Plumbing and Drainage Regulation 2018*, and the conditions of approval detailed below.
- 3. This approval, the conditions of approval and the Schedule comprise the entire Treatment Plant Approval document.
- 4. Any modification by the manufacturer to the design, drawings or specifications scheduled to this approval must be approved by the Chief Executive.

Conditions of approval

- 5. The manufacture, installation, operation, service and maintenance of the systems must be in conformity with the conditions of this Treatment Plant Approval.
- 6. The advanced secondary quality wastewater treatment system, which is an example of the approved systems, may only be used on premises that generate per day:
 - (a) a maximum hydraulic loading of 2,250 litres; and
 - (b) a maximum organic loading of 700grams BOD⁵
- 7. The system must continue to meet the requirements of advanced secondary quality wastewater treatment system, producing the following effluent quality:
 - (a) 90% of the samples taken must have a BOD⁵ less than or equal to 10 g/m³ with no sample greater than 20g/m³.
 - (b) 90% of the samples taken must have total suspended solids less than or equal to 10g/m³ with no sample greater than 20g/m³.
 - (c) 90% of the samples taken must have a thermotolerant coliform count not exceeding 10 organisms per 100 mL with no sample exceeding 200 organisms per 100 mL.
 - (d) Total chlorine concentration must be between 0.5g/m³ and 2.0 g/m³ in four out of five samples taken.
 - 8. Each system must be serviced in accordance with the details supplied in the owner's operation and maintenance manual.
 - 9. This approval does not extend, apply to, or include the land application system used in conjunction with an approved system installed on premises.





- 10. Each system must be supplied with
 - (a) a copy of this Treatment Plant Approval document;
 - (b) details of the system;
 - (c) instructions for authorised persons for its installation;
 - (d) a copy of the owner's manual to be given to the owner at the time of installation; and
 - (e) detailed instructions for authorised service personal for its operation and maintenance.
- 11. At each anniversary of the Treatment Plant Approval date, the supplier must submit to the Chief Executive a list of all systems installed in Queensland during the previous 12 months. Where the Chief Executive is notified of any system failures the Chief Executive may randomly select a number of installed systems for audit. The Chief Executive will notify the supplier's nominated NATA accredited laboratory which systems are to be audited for BOD⁵ and TSS. The sampling and testing of the selected systems, if required, is to be done at the supplier's expense. The following results must be reported to the Chief Executive;

a)Address of premises;

b)Date inspected and sampled;

c) Sample identification number;

d)BOD^₅ for influent and effluent; and

e)TSS for influent and effluent.

12. The Chief Executive may, by written notice, cancel this approval if the manufacturer/supplier fails —

a) to comply with one or more of the conditions of approval; or

b)within 30 days, to remedy a breach, for which a written notice been given by the Chief Executive.

- 13. This approval may only be assigned with the prior written consent of the Chief Executive.
- 14. This approval expires on 01 January 2024 unless cancelled earlier in accordance with paragraph 12 above.

Treatment Plant Approval Approved by: Stacey McInnes Delegated Authority

Department of Housing & Public Works



Stacey McInnes

A/Director Plumbing, Drainage and Special Projects Building Legislation and Policy Date approved: 14 July 2020

Level 7, 63 George Street Brisbane GPO Box 2457, Brisbane Qld 4001 **Telephone** +61 7 3008 2557

Facsimile +61 7 3237 1248 Website www.hpw.gld.gov.au

ABN 61 331 950 314



TREATMENT PLANT APPROVAL No. 13/2020 Plumbing and Drainage Act 2018

SCHEDULE

Attachment 1

Drawings and Specifications for the

Aqua-Nova model 10114Z

Treatment Plant Approval Approved by: Stacey McInnes Delegated Authority Department of Housing & Public Works



Schedule 1: Specification

Aqua-Nova (10114Z) Aerated Wastewater Treatment System

The Aqua-Nova (10114Z) Aerated Wastewater Treatment System (AWTS) is designed to treat the wastewater from a residential dwelling occupied by a maximum of 15 persons or a small commercial premises that generates a maximum of 2250L/day to a Advanced Secondary Standard

The Aqua-Nova (10114Z) is contained in 3900L Concrete Septic Tanks and collection wells each with design capacities as set out below.

Operation

The Aqua-nova treatment plant is a two tank system.

Wastewater flows into the first tank (Primary Tank). This tank acts as a septic tank removing most solids and fats/oils. Solids retained in this tank are digested anaerobically.

Water from this tank flows to a second tank. This tank is aerated and fitted with submerged media. Aerobic bacteria grow on the media to biodegrade the remaining contaminants in the wastewater. Bacteria occasionally slough off the media and become suspended in the water.

Aeration is continuous.

Water then flows to a clarifier where the solids are allowed to settle. These solids are pumped back to the start of the treatment plant.

Clarified wastewater is chlorinated and pumped through a Granular Media Filter prior to irrigation.

Treatment Plant Approval Approved by: Stacey McInnes Delegated Authority Department of Housing & Public Works



Configuration

Design capacities	2 x 3900L
primary sedimentation	3587L
 secondary treatment aeration chamber sedimentation inigation 	2630L 430L 393L
emergency storage	1040L
operational water level primary secondary	(mm) 1500 1400

The Aqua-Nova AWTS is assembled in the following configuration

- A chlorine disinfection unit is installed on the outlet of the clarifying chamber.
- Air is supplied to the contact aeration chamber by a Nitto LA120 air blower or equivalent, producing an airflow of a nominal 120 litres/minute at 1.3 m water depth.
- A Davey model D-25A submersible irrigation pump or equivalent is installed in the irrigation chamber for standard above ground irrigation. Type of pump may vary if subsurface irrigation is employed or the disposal area is significantly above the location of the sewage treatment plant.
- Label will be located on the Control Box of the system and have the following information provided
 - System Name
 - Model No.
 - Approval Number
 - Design Hydraulic Capacity
 - Date of Manufacture
 - Top Load Limitations
 - Weight of Tank
 - Lifting/Transport Instructions

The name and telephone number of an appropriate service representative to be contacted in the event that a problem with the plant occurs.

The website from which the documentation can be downloaded during the design life.

> Treatment Plant Approval Approved by: Stacey McInnes Delegated Authority Department of Housing & Public Works





Trea Approved Delegated Departme	tment Plant App by: Stacey McInnes Authority nt of Housing & Pul	roval	Queensland Government		
EFFLUENT APPLICATION/IRRIGATION SYSTEM TO BE AS PER INSTRUCTIONS CHAMBER OR DESIGN PROVIDED WITH EACH INDIVIDUAL SYSTEM.					
PUMPOUT	1250				
IBER					
BACKFILL TO RIM OF TANK WITH SELECT BACKFILL ONLY					
IL EMERGENCY S ACITY PRIOR TO CLARIFICATION RRIGATION TANK	TORAGE OVERFLOW , CONTACT, SHOWN				
T CHLORINATOR					
IA MEDIA					
SIBLE PUMP AS I	PER TABLE				
MIN THK SAND BED					
IN TATLEBUOLK			80	5/5/10	
	MATERIAL	MASS	SEALE 1:25	PRCI NO.	
RHARD INDUST	RIES PTY LTD	405 NEV Phi 10	NMAN RCVD, GEEBI 7 1 3637 5444	MG, (LLD, 4034	
FAX . (07) 3265 2111 .					
MP - 6	5640		1	6/5/10	



۰.





- , 🖍

	FIRST APPROVED FOR MANUFACTURE	EVERHA
DEV	ISSUE REVISION:	ALD CONCRECCE I
202	DAT5:	FLE
ח	APP'D BY:	DRAWNS TAL
		199

. .

